のなり

Diag. Cht. Nos. 1001-3 & 1241-2

NOAA FORM 76-35A

U.S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEY

DESCRIPTIVE REPORT

(HYDROGRAPHIC)

Type of Survey Hydrographic WH-40-2-74
Office No
LOCALITY
StateGeorgia
General Locality Georgia Coast-Offshore
Locality East of Sapelo Island
19 74
CHIEF OF PARTY
LIBRARY & ARCHIVES
DATE

☆ U.S. GOV. PRINTING OFFICE: 1976-669-441

	C&GS-537
7/W_##\	

U.S. DEPARTMENT OF COMMERCE ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION COAST AND GEODETIC SURVEY

REGISTER NO.

H-9429 Not-Issued

HYDROGRAPHIC TITLE SHEET

INSTRUCTIONS - The Hydrographic Sheet should be accompanied by this form, filled in as completely as possible, when the sheet is forwarded to the Office.

FIELD NO.

WH-40-2-74

State	Georgia
General locality	Georgia Coast-Offshore
Locality	East of Sapelo Island
Scale	1:40,000 Date of survey 7 April - 17 May 1974
• '	ted 29 Oct 1973 (see remarks) Project No. OPR-436-WH-74
Vessel	Ship WHITING
Chief of party_	CDR Robert A. Trauschke
Surveyed by	CDR R.A. Trauschke, LCDR Daniels, LT Theberge, LT Meyers, ENS Gastaldo, ENS Perrin, ENS Gullekson, ENS Bennet, In
	scaled byShip personnel
Graphic record c	checked byShip personnel
•	CALCOMP AMC Automated plot by WHITTING System
Soundings penci	
commungs benef	iled by WIITING Shipboard System CALCOMP AMC
	iled by WHITING Shipboard System CALCOMP AMC
Soundings in REMARKS:	Time meridian of this survey was 0° Project Instructions
Soundings in REMARKS:	Time meridian of this survey was 0° Project Instructions 29 October 1974 are supplemented by Change No. 2 to Project
REMARKS:	Time meridian of this survey was 0° Project Instructions 29 October 1974 are supplemented by Change No. 2 to Project etions dated Dec 10, 1973 and Change No. 2 to Project Instruc-
Soundings in REMARKS:	Time meridian of this survey was 0° Project Instructions 29 October 1974 are supplemented by Change No. 2 to Project 20 October 1974 are supplemented by Change No. 2 to Project 21 October 1974 are supplemented by Change No. 2 to Project Instructions 22 October 1974 are supplemented by Change No. 2 to Project Instructions 23 October 1974 are supplemented by Change No. 2 to Project Instructions 24 October 1974 are supplemented by Change No. 2 to Project Instructions 25 October 1974 are supplemented by Change No. 2 to Project Instructions 26 October 1974 are supplemented by Change No. 2 to Project Instructions 27 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 29 October 1974 are supplemented by Change No. 2 to Project Instructions 20 October 1974 are supplemented by Change No. 2 to Project Instructions 20 October 1974 are supplemented by Change No. 2 to Project Instructions 20 October 1974 are supplemented by Change No. 2 to Project Instructions 20 October 1974 are supplemented by Change No. 2 to Project Instructions 21 October 1974 are supplemented by Change No. 2 to Project Instructions 22 October 1974 are supplemented by Change No. 2 to Project Instructions 23 October 1974 are supplemented by Change No. 2 to Project Instructions 24 October 1974 are supplemented by Change No. 2 to Project Instructions 25 October 1974 are supplemented by Change No. 2 to Project Instructions 26 October 1974 are supplemented by Change No. 2 to Project Instructions 26 October 1974 are supplemented by Change No. 2 to Project Instructions 27 October 1974 are supplemented by Change No. 2 to Project Instructions 27 October 1974 are supplemented by Change No. 2 to Project Instructions 27 October 1974 are supplemented by Change No. 2 to Project Instructions 27 October 1974 are supplemented by Change No. 2 to Project Instructions 27 October 1974 are supplemented by Change No. 2 to Project Instructions 27 October 1974 are supplemented by Change N
Soundings in REMARKS:	Time meridian of this survey was 0° Project Instructions 29 October 1974 are supplemented by Change No. 2 to Project 20 October 1974 are supplemented by Change No. 2 to Project 20 October 1974 are supplemented by Change No. 2 to Project 21 October 1974 are supplemented by Change No. 2 to Project Instructions 22 October 1974 are supplemented by Change No. 2 to Project Instructions 23 October 1974 are supplemented by Change No. 2 to Project Instructions 24 October 1974 are supplemented by Change No. 2 to Project Instructions 25 October 1974 are supplemented by Change No. 2 to Project Instructions 26 October 1974 are supplemented by Change No. 2 to Project Instructions 27 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Project Instructions 28 October 1974 are supplemented by Change No. 2 to Proje

A. PROJECT

This project was completed in accordance with Project Instructions for OPR 436 dated October 29, 197 3 and supplemented by Change No. 1 to Project Instructions dated December 10, 1973 and Change No. 2 to Project Instructions dated February 8, 1974.

B. AREA SURVEYED

The area surveyed is east of Sapelo Island, Georgia and is bounded by lines joining the following points.

1	081° 00	w8. '	31°	36 t	.6N
2	081° 02	.ow	31°	31'	.ON
3	081° 08	· .6W		201	
4	080° 43	' .3W	31°	20 '	.5N
5	080° 43			29.¹	
6	080° 42			29 1	
7	080° 42	.4W	31°	36 t	.6N


Soundings were taken during the period from April 7, 1974 to May 17, 1974.

This survey junctions on the north with H-9184 of scale 1:40,000 completed by the WHITING in May 1974. The survey is bounded on the east by #9299 of scale 1:80,000 completed in 1972 and H-9375 of scale 1:80,000 completed in 1974. The junctions to the south will be with WH-40-3-74 which is in progress-H-9430(1974). On the west with H-9452(1974)1:20,000 and H-9473(1974)1:20,000 c. SOUNDING VESSEL

The WHITING made all soundings.

D. SOUNDING EQUIPMENT

Two Ross Depth Recorders, Model 5000, serial numbers 1049 and 1055 were used in waters varying from 28 to 72 feet in depth. Corrections were made by computations from temperature, depth and conductivity data with leadline comparisons. See "Echo Sounder and Velocity Correction Report" in Appendix 11.



E. SMOOTH SHEET

The smooth sheet will be plotted by the Processing Division at the Atlantic Marine Center.

Accompanying this report are two mylar plotter sheets WH-40-2N-74 and WH-40-2S-74 containing main scheme hydrography and cross lines, and two overlays containing developments, splits, bottom samples and pre-survey review item locations.

The discussion of calibration error applied to the "boat smooth" sheet is in Appendix 1, "Electronic Control Report".

F. CONTROL

The electronic control for this survey was the Sea-Fix(Wyperbolic Mode) System as modified by Odom Offshores Industry. See Appendix / 1, "Electronic Control Report" for location of the stations, Sea-Fix specifications, and calibration procedures.

AMC located all stations.

G. SHORELINE

This survey area contains no shoreline.

H. CROSSLINES

There are no major discrepancies between crosslines and main scheme hydrography. Differences vary between one and / two feet. This is accounted for by wave action.

Crosslines are approximately 9 per cent of main scheme / hydrography.

I. JUNCTIONS

(H-9429) WH-40-2-74 junctions on the north with contemporary survey 1:40,000 H-9144 completed May 2, 1974. Hydrography was continued immediately from one sheet to the next and there are no discrepancies in soundings.

The northern portion of the eastern border junctions with PIERCE 1:80,000 survey H-9299 completed in 1972. As H-9299 is a complete survey, TRA and velocity correctors are applied while they are not applied to WH-40-2-74 soundings. The appropriate corrections were applied by inspection.

Soundings from the two surveys generally agree. In the vicinity of 31° 22' .0N, 080° 43' .5W the WHITING soundings vary from 740 to 769 feet while the PIEROE soundings [#9375(1974)] vary from 601 to 727 feet. This area lies in a slight trough in which there has probably been some current caused erosion.

The southern portion of the eastern border junctions with Mt. MITCHEL 1:40,000 survey H-9375 completed in 1974. Velocity corrections were not applied to the Mt. MITCHEL soundings so only a final TRA correction for the WHITING need be applied in comparing soundings. Agreement between the two surveys is excellent with sounding seldom varying more than one foot.

See Appendix 11 for TRA and velocity corrections.

J. COMPARISON WITH PRIOR SURVEYS

Pre-survey review item positions are listed on the following page. The number of code item is plotted on the boat sheet overlay and is used to identify the item on the presurvey review sheets. Final TRA and velocity corrections for the reviewed depths were made by inspection. Further investigation was not required for any item. It should be noted that the bottom consists of sand ridges subject to continuous shifting.

- #45 Pre-survey review item added from H-3983: This is a 56 foot sounding which was found. The shoalest sounding in the area is 552 feet located 1.0 miles southwest. The recommendation is to chart the shoaler sounding. Concur
- #46 Pre-survey review item added from H-3983: This is a 52 foot sounding which was not found. The recommendation is to chart shoalest sounding in the area. Concur
- #47 Pre-survey review item added from H-3983: This is a 44 foot sounding which was found. As there is a 4342 foot sounding located -3-miles south, V the recommendation is to chart the shoaler sounding Concur
- #49 Pre-survey review item from C&GS Chart 1241: This is a 39 foot sounding which was not found. The recommendation is to chart the shoalest sounding in the area. Concur 37 ft depth found

- #50 Pre-survey review item from C&GS Chart 1241: This is a 29 foot sounding which was found. There are no shoaler soundings in the area. The recommendation is that this lesser present survey soundings be charted.
 - #51 Pre-survey review item from C&GS Chart 1241: This is a 42 foot sounding which was not found. The recommendation is to chart the shoalest sounding in the area.44 Concur
 - #52 Pre-survey review item from C&GS Chart 1241: This is a 35 foot sounding which was not found. The recommendation is to chart the shoalest sounding in the area. Concur 36's conding 0.2 mile southeast.
 - #53, #56, #57, #58 Pre-survey review item J from Local Notice to Mariners No. 39 of 1971: These are reported artificial fishing reefs marked by four can bouys. Inspection of the fathograms yields no indication of reefs at positions #53, #56, and #57. There is a slight trace of something possibly rising about a foot from the bottom in the vicinity of position #58. Further investigation was not warranted. There are no bouys at these locations. It is recommended that the fish havens be deleted from retained on the chart as per reporting source.
 - #054 Pre-survey review item added from H-3983: This is a 69 foot sounding which was not found, although 69 foot soundings exist 1. mile to the west and 0.7 mile to the south. The recommendation is to chart the shoalest present survey soundings in the area.
 - #055 Pre-survey review item added from H-3983: This is a 68 foot sounding which was located .2 miles east. As shoaler soundings exist nearby the recommendation is to chart the shoalest soundings in the area.
 - #059 Pre-survey review item from C&GS Chart 1241: This is a 63 foot sounding which was found .4 miles southeast. As it is the shoalest sounding in the area the recommendation is to chart it. Revise chart to agree with the present survey.
 - #65 Pre-survey review item C&GS Chart 574: This item is a charted sounding of 29 feet which was not found recommendation is that the shoalest depth in the area be charted from the present survey.
 - #88 Pre-survey review item from C&GS Chart 574: This item is a charted sounding of 34 feet which was feet. However, a 3/23 foot soundings exists the soundings be charted. In the area.

 lesser present survey


COMPARISON WITH SURVEY H-3983 1:80,000 1916-1917:

The soundings of survey H-3983 are generally close to those of WH-40-2-74. Where there was a discrepancy of a few feet a sounding equal to that inspected on H-3983 could usually be found within several hundred meters of the selected position on WH-40-2-74. On the eastern side of the sheet several of the soundings from H-3983 exceeding 70 feet were not found.

Discrepancies are accounted for by the susceptibility of features on the sandy bottom to current induced migration.

PRE-SURVEY REVIEW ITEMS WH-40-2-74


<pre>Item #</pre>	<u>Latitude</u>	Longitude
046 047 049 050 051 052 053 055 055 055 055 055 055	31° 35' 05"N 31° 31' 24"N 31° 29' 53"N 31° 29' 30"N 31° 29' 05"N 31° 27' 06"N 31° 25' 55"N 31° 25' 55"N 31° 24' 46"N 31° 24' 40"N 31° 24' 40"N 31° 24' 45"N 31° 22' 45"N 31° 23' 51"N 31° 34' 55"N	080° 49' 18"W \ 080° 51' 30"W \ 080° 57' 30"W \ 080° 52' 14"W \ 080° 55' 14"W \ 080° 57' 00"W \ 080° 57' 00"W \ 080° 57' 42"W \ 080° 57' 12"W \ 080° 56' 31"W \ 080° 43' 54"W \ 081° 00' 24"W
088∽ 095	31° 23' 00"N 31° 21' 00"N	081° 03' 00"W / 081° 00' 47"W /
		· · · · · · · · · · · · · · · · · · ·



ington, D. C. by COMMERCE Tetary C. SURVEY

(Tybee Island to Doboy Sound)
soundings in 1811 - SCALE 1 80.000

C. & G. S. 1241



	167				Bl*er
120/: · · · · · · · · · · · · · · · · · · ·	, a a	, , , , , , , , , , , , , , , , , , ,	n	. //	
	/ · · · · · · · · · · · · · · · · · · ·	24 22			0a:
	4 14 14 14 14 14 14 14 14 14 14 14 14 14	n n			•
		19 26	· /	». »	
	10 10				<u></u>
	24 as 20	" (D),		(,	
		25	1	. ‡	165 .
		8 8		33	
	40	25 22 42		p 4 23	. "
-		25 24	22 22 24 24 24 24 24 24 24 24 24 24 24 2	.c> .	. Ju
	**************************************	27 22)	33 S	30/ 30 30 30 30 30 30 30 30 30 30 30 30 30	
Experiment Show		n n n /	34	× ×	
See O	; , , , , , , , , , , , , , , , , , , ,	19 / 25	" (Š)*."	33	
			33 / 36		
		25 25	23 / 26	•	
		22 24 24	33 /20 / 24	36 40	
		" "!;;	20	•	42 15
		* **	30 30 30	41	* 000
	- a	. н	16 /m	39 1974	CONTINU
	(a) (b) (b) (c) (c) (c) (c) (c) (c) (c) (c) (c) (c	e i a	<i>"</i>	.	" .
9 16 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			CHĂ	RT 574	31.
	e 9	1			
4.0		30			
		1	, n		•
	. 0("	» ,	37	fa	
e e	n , , , ,		n	44	
	D D		. 13		-
/ (a)	23	10.	· 34,		
		37	•	, w	
	35 30 30		# I	35 46 44 30	
		33	n	x e	35
	20 5.54	39	•		» »
e de la companya de l	* 0 /	ж		ų	-
And the second s	,		34	•	

COMPARISON WITH THE CHART

C&GS Chart 574 October 21, 1972: Soundings were generally in agreement with those on this chart. Where a discrepancy exists, charted soundings can usually be found on the boat sheet within several hundred meters of the charted position. Several developments were made on the western edge to determine the extent of shoaling near the shoalest charted soundings and near the shoalest main scheme soundings. A 29 foot(30 ft.on sounding was found at 31° 34185 NN, 081° 00° 35W approximately sheet) I mile south of a charted 29 foot sounding. The depth in between varies from 27s feet to 36 feet. None of the western developments revealed depths varying more than a few feet from those on the chart.

C&GS Chart 1241 July 7, 1973

The soundings on WH-40-2-74 also generally agree with those on C&GS 1241. Slight variations are attributed to the shifting of the sand ridges delineated on the boat sheet.

The Fish Haven Bouy "SLB" privately maintained and reported in Notice to Mariners, No. 3731973 to be at 31° 24' .5N and 080 521 . 6W was not found. It should not be charted. (See Review-sect 6-b)

L. ADEQUACY OF THE SURVEY

This survey is complete and adequate and should supersede all previous surveys.

M. AIDS TO NAVIGATIONN

Area of sheet

Bouy R"28" charted at 31° 28' .5N, 080° 54' .5W is located .4NM south of 31° 28' 07"N, 080° 54' 40"W. This aid adequately serves its purpose. pes. #5116

N. STATISTICS

51156 Number of positions: Miles of sounding lines: 3053 Number of bottom samples: 220.8 square miles

O. MISCELLANEOUS

The bottom samples indicate that the bottom is sand throughout the area of the survey in agreement with Chart 1241. West of longitude 080° 52° .0, the contours are gently sloping ridges and troughs treding toward the southeast. East of longitude 080° 52' .0, the ridges and troughs tend more toward the east as the bottom becomes more even with the reception of several isolated and very pronounced slopes in the vicinity of 31°26'N, 31° 32'N and 31° 34'N.

P. RECOMMENDATIONS

None

Q. REFERENCES

Electronic Control Report, OPR 436 WH-40-2-74 Echo-Sounder and Velocity Report OPR 436 WH-40-2-74

APPROVAL SHEET

Submitted by:

Brooford B. Heyers

Bradford B. Meyers LT, NOAA

James Hail Bennett Jr. James H. Bennett, Jr.

ENS, NOAA

Approved/Forwarded

Robert A. Trauschke Robert A. Trauschke

CDR, NOAA Commanding APPENDIX

LIST OF SIGNALS

Name	Location	Lat	itu	de	Lor	gitu	de
unknown	Mayport Naval Station, FL	30° 2	23 '	40.366"	081°	23'	41.056"
Radd 2, 1974	Tybee Island, GA	32° 0	11	12.30"	080°	50 '	35.22"
Savannah Offshore Tower	East of Tybee	31° 5	5 7 '	00.416"	080°	401	59.062"
1968 (The 1	name of Savannah its position are	Offsh curre	nore entl	Tower, 19 y subject	74 to co	onter	ntion)
Simon 1974	St. Simons,	31° (1 80	27.12"	08 1°	221	03.11"

ECHO-SOUNDER CORRECTION ABSTRACT

SHIP WHITING

WH-40-2-74

FROM

OT

VELOCITY TABLE

Day GMT 097 115402

GMT Day 137 08534 Table #1

Only one velocity table was needed to complete this boat sheet (See Appendix II Echo-Sounder and Velocity Correc-NOTE:

tion Report).

APPENDIX II

ECHO-SOUNDER AND VELOCITY CORRECTIONS REPORT

PROJECT OPR-436-WH-74 GEORGIA COAST

NOAA SHIP WHITING
ROBERT A. TRAUSCHKE, CDR, NOAA
COMMANDING

A. GENERAL DISCUSSION:

The hydrography for the boat sheet WH-40-2-74 of OPR-436-WH-74 was accomplished with the NOAA Ship WHITING. Ross model 5000 echo-sounders were used. Echo-sounder S.N. 1049 was used from the beginning of hydrography until Julian Day 121. Echo-sounder S.N. 1055 was used to completion of the sheet.

Echo-sounder operators made frequent checks for proper initial settings, and utilized the internal phase check. Both echo-sounders were initialized at zero feet.

B. VELOCITY CORRECTIONS:


Velocity corrections to depth soundings were determined from TDC cast data. Leadline comparisons were taken to validate the use of TDC velocity corrections. TDC casts were made on the eastern side of the sheet to encompass greater depths.

Computer program AM530 was used to calculate velocity of sound, and corrections to soundings from TDC data. The program uses input of salinity, temperature and depth from surface to depth. The TDC data was algebraically corrected in accordance with actual conditions. The program corrects for the vessel's draft. Graphs #1 and #2 show that over small changes in temperature and conductivity, the corrections to TDC observations are nearly constant. In the ranges we experience, the differences in corrections are negligible. Graph #3 shows that for the range we work (20°C to 28°C) the slope and placement of the curve closely approximates the real curve. The data for these graphs is from calibrations done by the National Oceanographic Instrumentation Center during this year's in-port period.

TDC casts were made on Julian Days 106, 121, and 137. The data from each of these casts is in the Appendix. Velocity correction tables and plots (Graph #4) of all three casts are on the following pages. At no depth is the discrepancy between plots greater than 0.6% of the depth so that averaging the three would cause them all to be well within 0.5% of the depth from the average. This is the largest discrepancy allowed by the Hydrographic Manual.

INSTRUMENT TEMPERATURE VS. ACTUAL TEMPERATURE (°C)


Graph #1



10 20 30 40


Actual Temperature °C

INSTRUMENT CONDUCTIVITY VS. ACTUAL CONDUCTIVITY (ms/cm)



10


0




VELOCITY CORRECTION TABLE

Day	Depth	Total Corrections
106	0.0 6.6 13.1 19.7 26.2 47.6 64.0	.00 .26 .53 .79 1.06 1.92 2.57
121	0.0 6.6 13.1 19.7 26.2 47.6 64.0	.00 .29 .59 .88 1.17 2.10 2.82
137	0.0 6.6 13.1 19.7 26.2 47.6 64.0	.00 .33 .66 .99 1.31 2.36 3.17
Average	0.0 6.6	.00 .2 5
	13.1	•29 •5 9
	19.7	•5 3
	26.2	1.18
	47.6	2.13
	64.0	2.85

(Let 1 inch equal 4 fathoms for deep water and 1 inch equal 0.4 fathom for shoal.)







U.S. DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration NATIONAL OCEAN SURVEY NOAA Ship WHITING

Date: June 10, 1974

To : LCDR Dale North

Chief of Processing

From: fec CDR Robert A. Trauschke, NOAA

Commanding Officer

Subj: Corrections to Descriptive Report WH-40-2-74

An error was found in descriptive report for WH-40-2-74. The error is in the echo-sounder and velocity corrections report. Two copies of the corrected pages are enclosed, and they should be substituted at the appropriate places in the report. Also enclosed is the velocity correction table.

VELOCITY TABLE LISTING

000022 0 0000 0001 000 293000 040274

000065 0 0002

000106 0 0004

000149 0 0006

000189 0 0008

000232 0 0010

000274 0 0012

000314 0 0014

000357 0 0016

000400 0 0018

000442 0 0020

000484 0 0022

000526 0 0024 -

000569 0 0026

000612 0 0028

000654 0 0030

000695 0 0032

000738 0 0034

999999 0 0036

TC/TI TAPE LISTING

000000 0 0012 0001 097 293000 040274

After averaging the correction values at each depth, these values were subtracted from the corresponding depth to obtain the echo-sounder depth versus the correction plot (Graph #5). This is the necessary plot used to generate the velocity table tape which is listed in the Appendix.

Velocity corrections were verified by leadline comparisons taken on Julian Day 106 and 121. The data is in the Appendix, and listed below are the results.

Lead Line	Velocity Corr.	Avg. Depth	% Discrepancy
106	3.0'	75.9	0.6%
121	2.7	70.01	1.3%

These leadlines are in good agreement with the velocity corrections used for this sheet. The larger discrepancy on Day 121 was probably due to the 2 ft. seas that day.

C. TRA CORRECTIONS

Settlement and squat observations were made on Ship WHITING 6 September 1973 (see <u>Fathometer and Velocity Report</u>, <u>Project OPR-436-WH-73</u>, <u>Coast of South Carolina and Georgia</u>). The results are as follows:

Full Speed .7 ft.
Reduced Speed .2 ft.

The WHITING's draft was measured during the times of hydrography. A draft of 10.0' was used in the hydroplot controller except at times of reduced speed, when 9.5' was used, or a -0.5' was used as the TRA correction on the corrector tape. This procedure eliminated the need for correcting for reduced speed soundings on the TC/TI tape. All ship TRA correctors are of the form:

TRA = Draft + S&S

= Hydroplot Draft + (Draft - Hydroplot Draft) + S&S

Full Speed:

Reduced Speed:

The above shows that only the sum of (Draft - 10.0') + 0.7' must be used on the TC/TI tape.

The average draft was calculated to be 10.5' (see Draft Data Table). The largest deviation for any cruise average was 0.2', which is only 0.6% of the minimum depth of hydrography. The value used on the TC/TI tape is:

TRA =
$$(10.5' - 10.0') + 0.7'$$

= 1.2'

The TC/TI tape is listed in the Appendix.

No echo-sounder initial corrections were necessary since the echo-sounder was initialed at zero feet and checked frequently.

DRAFT DATA

Date	Julian Day	Ship Load Note	Port	Stbd	Average	Draft - 10'
29 Mar.	088	After fueling	10.5'	10.81	10.6'	.61
15 Apr.	105	Before fueling	10.5'	11.0'	10.81	.81
 15 Apr.	105	After fueling	10.7'	10.7'	10.7'	.71
29 Apr.	119	Before fueling	10.3'	10.3'	10.3'	.3'
30 Apr.	120	After fueling	10.3'	10.7'	10.5'	. 51
13 May	133	Before fueling	10.5'	10.0'	10.21	.21
 13 May	133	After fueling	10.5'	11.0'	10.8'	.81
 20 May	140	After leadline	10.8'	9.81	10.3'	.31
		Average for period	3/29 to 5/	20	10.5'	.51
	,					
				·		

APPROVAL SHEET

Submitted by:

Edward D. Gullekson Edward D. Gullekson ENS, NOAA

Approved/Forwarded:

Robert A. Trauschke CDR, NOAA

Commanding Officer, NOAA Ship WHITING

TIDE NOTE

Predicted tides for this survey area were taken from the daily predictions of Savannah River entrance, Georgia, 1974, with appropriate differences applied for Savannah Light. The WHITING was furnished the following differences from Tides Branch for Savannah Light: -30 minutes for high and low, no correctors for height, and a .95 ratio. The following differences were used: -30 minutes for high and low, +0.0 feet for low, -0.4 feet for high, and a ratio of 1.0. The correctors for height were used because our software did not allow ratios with significant digits in the hundredths place.

The geographic locations for the tide gages encompassed in the survey area are as follows:

Name	<u>Latitude</u>	Longitude			
Ft. Pulaski, GA Savannah Beach, GA Savannah Light, GA St. Simons, GA Sapelo Island, GA	32° 02' .0N 32° 00' .3N 31° 57' .0N 31° 08' .0N 31° 23' .5N	80° 54' .1W 80° 50' .5W 80° 40' .5W 81° 23' .7W 81° 17' .0W			

The standard tide gage at Fort Pulaski, Georgia (Savannah River entrance) served as the basic control gage. Data from all stations except Savannah Light was sent directly to Tides Branch, Rockville Office C-331. Hourly heights from Marigrams for Savannah Light Bubbler gage were scanned by WHITING personnel and sent to C-331 along with ADR tapes for Savannah Light.

A copy of the letter to Chief, Tides Branch, C-331 is included in this report.

U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL OCEAN SURVEY

TIDE NOTE FOR HYDROGRAPHIC SHEET

Processing Division: Atlantic Marine Center:

Hourly heights are approved for Form 362

Tide Station Used (NOAA Form 77-12): Sapelo Island

Period:

April 7 - May 18, 1974

HYDROGRAPHIC SHEET: H9429

436 OPR:

Locality: Coast of Georgia

Plane of reference (mean lower low water): 3.9 ft.

Height of Mean High Water above Plane of Reference is 6.6 ft.

Remarks: Recommended zoning:

> 81⁰15' - 81⁰00' Direct *

81°00' - 80°50' Apply 0.94 range ratio -

80⁰50' - 80⁰35' Apply 0.88 range ratio - 3

James R Hulbard
Chief, Tides Branch

NOAA FORM 76-155 (11-72) N	ATIONAL	OCEANIC			ENT OF C			RYEY N	UMBER	
GEOGRAPHIC NAMES							Í	F-9429		
Name on Survey		OH CHART N	Prenous s	URVEY URVEY	ANGLE ANGLE ACM CORMAN	N LOCAL M	P.O. GUIDE	OR MAP	3. Light V	,5 ¹
	/A '	OH BOH	40. Co4	D	AC, MFC	^A /F	Q.O' GAY	H	,5. K	
ATLANTIC OCEAN										1
										2
										3
**************************************	<u> </u>	<u> </u>	 							4
									-	
	 	 								5
		 				-				6
			<u> </u>		 					7
		ļ .								8
									`	9
	ļ		ļ							10
				,						11
										12
										13
										14
										15
						 				
										16
										17
		 								18
		-	-			ļ				19
					A	SPLON	ed			20
					_ C	Jac. 8.	Han Geog 1975	ton	5	21
					41	ti	Com	7	1	22
					11	June	1015	Have	<u> </u>	23
					``	- WA	1113			24
					 					25

ATLANTIC MARINE CENTER APPROVAL SHEET FOR AUTOMATED SURVEY H-9429

A. All revisions and additions made on the smooth sheet during verification have been entered in the magnetic tape records for this survey. A new final position printout has/has not been made. A new final sounding printout has/has not been made.

Date: april 14,1975

Signed: william &

Title: Chief, Verification Branch

B. The verified smooth sheet has been inspected, is complete, and meets the requirements of the Hydrographic and AMC Manuals. Exceptions are listed in the verifier's report.

Date: april 14,1975

Signed:

& Red Worth Ir. Ledr. No

Title: Chief, Processing Division

HYDROGRAPHIC SURVEY STATISTICS HYDROGRAPHIC SURVEY NO. H-9429

RECORDS ACCOMPANYING SURVEY: To be completed when survey is registered.

RECORD DESCRIPTION			AMOUNT			RECORD	AMOUNT		
smooth sheet & 2-Overlays			1 BOAT SH		HEETS (3 parts)		1		
DESCRIPTIVE REPORT			1		OVERLAYS			2	
DESCRIPTION HOLLES	DEPTH RECORDS		CONT. ORDS	PRIN	FOUTS	TAPE R	OLLS	PUNCHED CARDS	ABSTRACTS/ SOURCE DOCUMENTS
ENVELOPES	78 K			32	•				1

Package" CAHIERS VOLUMES 1 BOXES

T-SHEET PRINTS (List)

SPECIAL REPORTS (List)

OFFICE PROCESSING ACTIVITIES The following statistics will be submitted with the cartographer's report on the survey

		AMOUNTS				
PROCESSING ACTIVITY	PRE- VERIFICATION	VERIFICATION	REV	IEW	TQTALS	
POSITIONS ON SHEET						
POSITIONS CHECKED		511 6			5116	
POSITIONS REVISED		5				
DEPTH SOUNDINGS REVISED		511				
DEPTH SOUNDINGS ERRONEOUSLY SPACED		0				
SIGNALS ERRONEOUSLY PLOTTED OR TRANSFERRED		0				
	TIME (MANHOURS)					
TOPOGRAPHIC DETAILS		0				
JUNCTIONS		4				
VERIFICATION OF SOUNDINGS FROM GRAPHIC RECORDS		40		:		
SPECIAL ADJUSTMENTS		4				
ALL OTHER WORK		100				
TOTALS		148	10.	5		
PRE-VERIFICATION BY		BEGINNING DATE	<u> </u>	ENDING	DATE	
H. R. Smith		July 15,	1974	18	Sept. 74	
VERIFICATION BY		BEGINNING DATE		ENDING	DATE	
R. G. Cram		15 Jan.	1975	23	Jan. 1975	
REVIEW BY		BEGINNING DATE		ENDING	DATE	
F.P. Saulsbury		NOV. 1975		ENDING Dec.	1975	

Cursory dropection 'X. W. Wellman

- Engle 840s 8-7-4, U.S. G.P.O. 1972-769-562/439 REG.#6

ullet
The Computer and Excess Sounding Cards for this survey have not been corrected to reflect the changes made to the Computer Card and Excess Card Printouts at this time of the review.
When the cards have been updated to reflect the final results of the survey, the following shall be completed:
CARDS CORRECTED
DATE TIME REQUIRED INITIALS
REMARKS:
REGISTRY NO. H-9429
The magnetic tape containing the data for this survey has not been corrected to reflect the changes made during evaluation and review.
When the magnetic tape has been updated to reflect the final results of the survey, the following shall be completed:
MAGNETIC TAPE CORRECTED
DATE 16-12-82 TIME REQUIRED INITIALS 98
REMARKS:

REGISTRY NO.

OFFICE OF MARINE SURVEYS AND MAPS

HYDROGRAPHIC SURVEYS DIVISION

MODIFIED HYDROGRAPHIC SURVEY REVIEW

REGISTRY	NO.	H-9429
----------	-----	--------

FIELD NO. WH-40-2-74

Georgia, Georgia Coast--Offshore, East of Sapelo Island

SURVEYED: April 7 - May 17, 1974

SCALE: 1:40,000

PROJECT NO.: OPR-436

SOUNDINGS: Ross 5000 Depth Recorders

<u>CONTROL</u>: Decca Sea-Fix

(Hyperbolic Mode)

Chief of Party	R. A. Trauschke
Surveyed by	R. A. Trauschke
•••••••••••••••••	
••••••••	
••••••••	B. B. Mevers
********************	E. Gastaldo
••••••••••••••	K. W. Perrin

Automated Plot by	Calcomp 618 (AMC)
Verified by	
Reviewed by	F. P. Saulsbury
•	Date: December 29, 1975
Cursory inspection madesurvey	K. W. Wellman
processing considered complete	July 23, 1979

1. Control and Shoreline

The origin of control is adequately described in part F of the Descriptive Report.

No shoreline falls within the limits of this survey.

2. Hydrography

- a. Depths at crossings are in good agreement.
- b. The usual depth curves are adequately delineated. Supplemental, dashed, and brown depth curves were added to emphasize significant isolated bottom features.

c. The development of the bottom configuration and the determination of least depths are considered adequate.

3. Condition of Survey

The sounding records, smooth plotting, and Descriptive Report are adequate and conform to the requirements of the Hydrographic Manual and the Instruction Manual - Automated Hydrographic Surveys with the following exceptions:

- a. The verifier apparently used uncorrected soundings from H-9462 (1974) in effecting the junction with the present survey. Appropriate revisions were effected during the review of the present survey.
- b. During field work, the hydrographer did not consider chart 11511 (formerly 573) which covers a portion of the present survey at a larger scale than chart 11509 (formerly 1241).

4. Junctions

An adequate junction was effected with H-9462 (1974) on the northwest. Due to the 2:1 scale difference, the overlapping depth curves in the area common to adjoining survey H-9462 are exaggerated on the present survey. They are, therefore, not in coincidence in accordance with the customary practice.

The junctions between the present survey and the following surveys are discussed in their respective Review Reports and require no further consideration:

```
H-9144 (1973-74) on the north
H-9299 (1972) on the east
H-9375 (1974) on the east
H-9430 (1974) on the south
H-9472 (1974) on the west
H-9473 (1974) on the southwest
```

5. Comparison with Prior Surveys

```
a. H-691 (1859) 1:20,000

H-728 (1860, 1906) 1:300,000

H-768 (1860) 1:500,000

H-3554 rec (1910-12) 1:50,000

H-3560 rec (1912-13) 1:100,000
```

These prior surveys comprise early coverage of the present survey area but are not discussed in the present review.

b. H-3983 (1916-17) 1:80,000

This prior survey covers the area of the present survey. A comparison of present survey depths with prior survey depths reveals areas of good agreement intermingled with depth differences generally within ± 8 feet and ranging to a maximum indication of present depths as much as 17 feet shoaler than prior depths. The noted depth differences are attributed to the natural shifting of the predominantly sand bottom sediments which is characteristic of the survey area.

Numerous bottom characteristics were carried forward from the prior survey to supplement the present survey. With the addition of the referenced bottom characteristics, the present survey is adequate to supersede the prior survey within the common area.

6. Comparison with Chart 11509 (formerly 1241), 12th Edition, Jan. 11, 1975
11510 (formerly 574), 8th Edition, Sept. 28, 1974
11511 (formerly 573), 7th Edition, March 22, 1975

a. Hydrography

The charted hydrography originates with the previously discussed surveys which require no further consideration, supplemented by soundings from the boat sheet (Bp's 89963-65) and verified smooth sheet of the present survey.

Attention is directed to the following:

- (1) It is noted that numerous charted soundings which originate with preliminary information from Bp-89963 (boat sheet) are generally shoaler than the corresponding depths on the final smooth sheet and should be revised accordingly.
- (2) The Obstruction, Fish Haven charted in the vicinity of latitude 31°24.50', longitude 80°52.60' originates with Local Notice to Mariners 33 of 1973. This feature is neither verified nor disproved by the present survey and should be retained as presently charted.

Except as noted in (2) above, the present survey is adequate to supersede the charted hydrography within the common area.

b. Aids to Navigation

The lighted whistle buoy R"2S" is located in latitude 31° 28.09', longitude 80°54.64' on the present survey, approximately 800 meters southwest of its charted location. In its present position, the buoy adequately serves its intended purpose.

The privately maintained Fish Haven Buoy "SLB" charted in the vicinity of latitude 31°24.5', longitude 80°52.6' from Local Notice to Mariners 33 of 1973 was not found by the hydrographer and is assumed to have been removed.

7. Compliance with Instructions

This survey adequately complies with the project instructions.

8. Additional Field Work

This is a good basic survey of the area and no additional field work is recommended.

Examined and Approved:

Acting Chief

Hydrographic Surveys Division

Associate Director

Office of Marine Surveys

and Maps

DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration

National Ocean Survey Rockville, Maryland Hydrographic Index No. 75 J 81" 50" 40 81"30 81,0005 80° 40' H-9314 INDEX HYDROGRAPHIC SURVEYS H-9363 32°00' Complete through August 1978 32°00′ 1955-1974 SAVANNAH - JACKSONVILLE GEORGIA-FLORIDA H-9145 F.E. No. 1 (2 parts) 50 W SOUND H-9144 HYDROGRAPHIC SURVEYS Date 1955 1973-74 1973 No H-8179 H-9144 H-9145 H-9197 H-9299 H-9462 10.000 40 1973 1971-73 1972 1973 1973 1973 1973 H-9299 H-9314 H-9363 H-9375 H-9375 H-9428 H-9429 H-9457 H-9457 H-9456 H-9299 H-9472 SAPEL 31°30′ 31°30 H-9429 9429 H-9460 H-9461 H-9462 H-9472 H-9473 H-9473 H-9474 F.E. No. 1 (2 parts) OUND H-9473 20 201 On Scales of 1:10000 6.34 inches = 1 statute mile 1.20000 3.17 inches = 1 statute mile H-9375 H-9430 10 Hickor ST. SIMON SOUND 31°00′ H-9458 31°00′ ST. ANDR W SOUND H-9449 H-9366 H-9428 40' . Callahan 30,30, ASSAU SOUND 30°30′ H-9474 Q. H-9373 JACKSONVILLE 40 81*301 81°00'

A5324

RECORD OF APPLICATION TO CHARTS

FILE WITH DESCRIPTIVE REPORT OF SURVEY NO.

77	^	12	^
UL	u		9
n =	72		. 7

INSTRUCTIONS

A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.

1. Letter all information.

2. In "Remarks" column cross out words that do not apply.

3. Give reasons for deviations, if any, from recommendations made under "Comparison with Charts" in the Review.

CHART	DATE	CARTOGRAPHER	REMARKS
<u> </u>	ļ		Part Part States After Verification Review Inspection Signed Via
574	6-9-75	D. R. CORDTS	
			Drawing No. Before App'd Critical Corr's
	سد در ر	D 0 00000	TWH Part Beter After Verification Review Inspection Signed Via
1242	6-17-75	D. R. CORDTS	The second secon
			HPPO CHIICAL CONTS
			7-15
104/	8-9-75	& Bodownon	Full Part Before After Verification Review Inspection Signed Via
			Drawing No. Before Applied Critical
	·		corr. thru cht 574 & Port direct
573	8-20-75	hul years	Full Part Before After Verification Review Inspection Signed Via
		0.7	Drawing No. 14 + 14M
1111	10-21-75	Shrall Korll	Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Mier Vendication Review bofore
574	6/3/76	Towns ALGUNDER	Full Past Before After Verification Review Inspection Signed Via
(11510)	0/0/16		Drawing No. Adequately applied survey before
(11010)			Inspection (Raised star within survey limits)
1242	0/01/7/	TONINIE ANNWA	
1242	0/24/16	10M1418 FREENOUSE	Drawing No. Adequately applied survey before
	<u> </u>		Inspection Jackson Believe
		10 D 0 0	Full Page Before After Verification Review Inspection Signed Via
1241	12jan.77	Max. Radichertal	1 400 400 1
			Drawing No. CATRGORY 1, SCOPE PROJECT
			Alegan to by
11480	6-10-80	alle John	Full Part Refore After Verification Review Inspection Signed Via
			Drawing No. 32
			Adequitly
11009	6-18-82	Butenla	Full Part Defore After Venification Review Inspection Signed Via
			Drawing No. 48 thus 1480
		•	
<u> </u>			
-			
-			
L	<u> </u>	L	